




Summer 2019 Internship WRPS Test Bed Initiative (TBI)

Jason Soto (DOE Fellow)

DOE-FIU Science and Technology Workforce Development Program
Applied Research Center
Florida International University

FLORIDA INTERNATIONAL UNIVERSITY





Background




- Goal of Hanford Cleanup
 - Prevent the release of nuclear waste into the environment
 - Convert the Hanford Site into a nature reserve and national park.
- Role of WRPS
 - Safely and efficiently manage the waste stored in the underground tanks





Project Description

- Problem
 - Tank waste contains substantial amounts of Cesium
 - Inefficient to vitrify
 - Affects glass properties
 - Problematic to grout
- Cesium 137
 - Radioactive isotope
 - Half life of 30 years
 - Chemically active
 - Gamma rays





Scope/Objective

- Develop a tool to extract cesium from tanks
 - More waste can be vitrified at a time
 - Speeds up cleanup process
 - Lowers overall costs

- My role
 - Design Engineering Intern
 - SolidWorks Design




Figure 1.
Diagram of a Double Shelled Tank



Method / Approach

Waste Process

- Waste pumped through the Ion Exchange Column (IXC).
- Cesium reduced waste is destined for vitrification or grouting.
- Cesium saturated filter encapsulated in storage cask.

Project Stages

- Stage1 - Completed
 - Experimental test
 - 3 gallons of waste treated
- Stage2 - In Design Phase
 - Scaling test
 - 2000 gallons of waste treated
- Stage3 - Future
 - Full scale operation



Figure 2.
Hanford Vitrification Canisters



Method / Approach

FIU

 Applied Research
Center

Design Requirements

- **Shielding**
 - Cesium decay produces gamma rays.
 - Based on expected concentration of Cesium, 8" of steel plate or 10" of steel shot required to protect workers.
- **Shine Paths**
 - Overlapping components prevent radiation from shining through cracks.
- **Manufacturing**
 - All the parts must have a manufacturing method in mind.
- **Venting**
 - Radioactive materials produce hydrogen, which must be vented.




Figure 3.
Engineering drawing of IXC endcap



Preliminary Results/Discussion




Figure 4.

Conceptual Design of IXC Extraction Tool




Figure 5.

Detail Design of IXC Storage Cask



Preliminary Results/Discussion




Figure 6. Detail Design Showing Cask Door Iterations



Conclusions

- Cask design has advanced considerably
- Other engineers are working on the various components
- Design work is more challenging when split up
- Stage 2 will be taken to 90% completion



Future Work

- Stage 2 Design
 - Finalize design
 - Tolerances/Clearances
 - Structural analysis
 - Approval
- Stage 2 Testing
 - Dry runs
 - Problem scenarios
- Stage 3 Designs
 - More Integral Approach
 - Cask swapping system




Figure 7.
Early Concept of Stage 3 Design



Acknowledgements

- **Mentors**
 - Matthew Garlick
 - Fred Sijgers
 - Dr. Leonel Lagos
- **DOE-FIU Science and Technology Workforce Development Program**
- **Sponsored by the U.S. Department of Energy, Office of Environmental Management, under Cooperative Agreement #DE-EM0000598.**